



Bid Package #15 Storefront/Curtainwall.

**Exhibit B**

Subcontract Scope of Work

Job Number:

Job Name: Columbia Street West – Ft. Wayne

Subcontractor:

Scope of Work: **Storefronts**

**GENERAL SUMMARY**

Maintain fences, barricades, guard rails, caution tape, silt fence & all soil control measures, gravel construction entrances/drives etc. If these items are damaged or removed by your forces (by accident, or for execution of work) they are to be reinstalled by your forces to an acceptable condition.

All deliveries and staging of materials must be coordinated with the Superintendent.

Maintain cleanliness of roadways to the satisfaction of Model Construction, neighborhood, and local authorities for the duration of your work on site. Subcontractor is responsible for cleaning dirt/debris from road if it is caused by your men, equipment, trucks, etc. If dirt/debris is tracked on the road and not cleaned by end of the work, Model Construction will clean and subcontractor will be back charged. (Model Construction will notify subcontractor and allow reasonable time to clean prior to assuming responsibility of cleaning).

Provide daily clean-up of all construction debris and “personal trash” (lunch wrappers, bottles, etc.) generated by your crew. Clean up after every workday and take trash to the proper dumpster before going home. If the job site is not in a neat and orderly condition, then all contractors on the jobsite will be responsible to pay for the cost plus fee to have a third party contractor make the job site clean, neat and orderly.

All MODEL CONSTRUCTION jobsites are TOBACCO FREE. All smoking, dipping, chewing, etc. must be done off site, in area designated by Model Construction Superintendent. Please inform your crew(s), as this will be enforced.

Temporary restrooms are provided by Model Construction.

All reference to “General Contractor”, Trade Contractor, or “Subcontractor” in the construction documents shall mean Trade Contractor as outlined in this scope of work/contract.

All work shall be performed by OSHA regulations and standards. All safety issues are to be corrected and paid for by this subcontractor.

All workers on Model Construction Job Sites should be OSHA ten hour trained or have the basic knowledge of OSHA laws and regulations.

All Job-Specific SDS Sheets for this Work Scope must be submitted to the Model Project Manager PRIOR to the start of work.

Subcontractor Initials \_\_\_\_\_

# model construction

Weekly subcontractor meeting will be held in the job office. These meetings are MANDATORY! At least one member from the subcontractor (foreman, project manager, or someone with decision making authority) must be in attendance starting two weeks prior to the scheduled start date, and throughout the duration of your scope of work.

Working hours for this project are established as 7:00 AM to 3:30 PM Monday through Friday. If subcontractors desire to work outside of these hours, prior approval must be granted by Model Construction superintendent. Contractors shall be expected/permitted to work Saturday or Federal Holidays as necessary to maintain the progress of the construction schedule.

All work to be in compliance with the complete contract documents (plans and specifications). Documents can also be examined at the Model Website (see below).

Any work not covered in the base contract must be approved by Model Construction before subcontractor proceeds with work. A daily ticket must be signed by Model superintendent for all extra work. All extra tickets must be included in a **Change Order Request** and submitted on a weekly basis. **No** compensation will be paid to subcontractor for extra work until it is signed by the subcontractor and Model Construction. Approved Change Order Requests are to be submitted to the Project Manager on Model's Change Order form **within Two Weeks** of the change order being approved or work is completed.

Proactive thinking and coordination with Model Construction and other subcontractors is expected and required throughout this project.

Any functioning system turned off or disconnected during the day must be put back in service by the end of the work day. Work day is to be considered day or evening shift depending on where the work is taking place.

Provide close out documents, spare parts, O & M manuals, warranty, etc. upon completion of the scope of work.

Provide accurate As-Built drawings.

Provide OSHA 300A at the end of this job documenting the hours logged by workers on the jobsite and any incidents that occurred on the jobsite.

Subcontractor is to provide a 1 year warranty for all work performed, stating on the day the certificate of occupancy is issued. This 1 year warranty must be officially submitted to Model Construction at the end of the project on company letterhead.

Contractor shall visit site and become familiar with existing conditions as they relate to the proposed work prior to submitting bid, ordering materials, etc.

Drawings and dimensions are plus/minus. Contractor responsible for verifying existing conditions, dimensions, etc., prior to commencing work. Report substantial discrepancies to Model Construction immediately, before continuing with work. Do not scale drawings.

Each contractor responsible for performing work according to local, state and national codes, as well as other regulations which apply to such work.

**Removal or cutting of structural members is not permitted unless shown on the drawings.** Consult with Model Construction regarding repair or removal of structural items.

Materials to be installed must conform to the manufacturer's recommendations.

Hard hats, work boots, protective eyewear and gloves are required for all personnel on-site.

Subcontractor Initials \_\_\_\_\_

# model construction

Final Payment will be paid after contractor complies with submitting its completed company punch list, submitting completed signed copies of Model Construction punch lists and providing all warranty paper work to Model Construction.

Smoking, eating and drinking on-site is prohibited.

**This is not a tax exempt project. Include all applicable taxes.**

**Prevailing Wages do not apply.**

**Each Subcontractor to provide a written detailed plan on how they will obtain Section 3 involvement in this Project. Plan will need to be updated on a MONTHLY basis.**

Model at its own discretion, may assign this subcontract, in total, to the Construction Manager. At time of assignment the General Contractor assumes all rights and privileges granted to Model by this subcontract. Subcontractor will be notified in writing within 5 working days of the assignment.

All work shall be coordinated and scheduled by the forth coming attached project schedule (Exhibit C) and managed through General Contractor.

## SUMMARY

Provide all labor, material, equipment, supplies, taxes, insurances, supervision, inspections, manufacturer's warranty and permits to perform the Storefront/Curtainwall Work for The Columbia St. West project in Ft. Wayne, Indiana.

The Buildings, and address included in this work are:

<b>133-135 W. Columbia St.</b>	<b>611 S. Harrison St.</b>	
<b>613 S. Harrison St.</b>	<b>617 S. Harrison St.</b>	<b>Ft. Wayne, IN 46802</b>

**All specifications, manufacturers, notes, and details are included in the drawing set. If additional clarification is required, it is your responsibility to contact Model Construction during the bidding process and request that clarification.**

**The General Specifications (Division 1) are spelled out above and shall become a part of any contract.**

Specifications directly applicable to this scope of work:

**Division 00 – All**  
**Division 01 – All**  
**Division 03 – All**  
**Division 08 – 08 41 13 - ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS**  
**08 44 13 - GLAZED ALUMINUM CURTAIN WALLS**  
**08 80 00 - GLAZING**

This contract specifically includes, but is not necessarily limited to the following:

- A. Coordinate and follow schedule. Working closely with site superintendent is a must.
- B. Furnish and install all aluminum storefronts/curtainwall and glass as noted on the drawings. Provide replacement glass as identified
  - a. Provide storefront in kind as an alternate at all curtainwall locations.
- C. Caulk interior and exterior of all items provided by this bid package.

Subcontractor Initials \_\_\_\_\_

# modelconstruction

- D. Contractor responsible for removing and disposing of existing or temporary door / window.
- E. Provide all hardware as specified for all openings in the work of this bid package. Including electronic hardware. Provide construction cores all keyed alike. Permanent cores by others.
- F. Furnish and install all miscellaneous glass and glazing requirements in any location as shown on the door/hardware schedule and elevations. Provide fire-rated and tempered glass as specified.
- G. Painting and prepping of historic components are not included in this BP.
- H. Windows, both replacements and rebuilds, are NOT included in this BP.
- I. If a new unit cannot be completed before end of day, opening needs to be left in a secure condition where no one can get inside during "off hours."
- J. **Lead:** For the purposes of this project, all existing painted/coated building materials are assumed to be lead containing, including but not limited to paints, stains, or other coatings. Work involving materials containing or coated with lead (Pb), must be performed in accordance with EPA's RRP regulations. Prior to the start of activities involving lead, the contractor must provide proof of current OSHA training for each person involved with lead activities, and that each person has written evidence of their ability to properly don the necessary respiratory protection if needed.
- K. Prior to work a lead scope and work plan must be submitted to Model Construction.
- L. Provide all necessary flashings for a complete weathertight system.
- M. Provide proper aluminum thresholds at all door areas. Thermally broken if required.
- N. Furnish and install all 'Chicago windows' per drawings.
- O. This scope of work includes the implementation and continued use of PROCORE and its safety/collaboration tools throughout the project. It is preferred that each contractor has at least one tablet or at minimum one smartphone, loaded with the program, on the job at all times.