

OUTLINE SCOPE OF WORK

BID DOCUMENTS:

1. The Crossroads Center – Invitation to Bid
2. The Crossroads Center – Outline Scope of Work
3. The Crossroads Center – Permit Drawings prepared by EMBOSS Design dated 8/9/24
4. CSI Inc.'s Geotechnical Report dated 1/4/2023
5. Westech Pre-Demolition Asbestos Survey dated 2/9/2024

GENERAL SCOPE SPECIFICALLY PERTAINING TO CROSSROADS CENTER`:

1. **Subcontractors are wholly responsible for delivery, unloading, and shakeout within the building.**
2. **Prevailing Wage Rates do NOT apply.**
3. **Project is Tax Exempt.**

GENERAL SCOPE OF WORK (Applicable to all Subcontracts):

1. Maintain fences, barricades, guard rails, caution tape, silt fence & all soil control measures, gravel construction entrances/drives etc. If these items are damaged or removed by your forces (by accident, or for execution of work) they are to be reinstalled by your forces to an acceptable condition.
2. All deliveries and staging of materials must be coordinated with the Superintendent.
3. Maintain cleanliness of roadways to the satisfaction of Model Construction, neighborhood, and local authorities for the duration of your work on site. Subcontractor is responsible for cleaning dirt/debris from road if it is caused by your men, equipment, trucks, etc. If dirt/debris is tracked on the road and not cleaned by end of the workday, Model Construction will clean, and subcontractor will be back charged. (Model Construction will notify subcontractor and allow reasonable time to clean prior to assuming responsibility of cleaning).
4. Provide daily clean-up of all construction debris and "personal trash" (lunch wrappers, bottles, etc.) generated by your crew. Clean up after every workday and take trash to the proper dumpster before going home. If the job site is not in a neat and orderly condition, then all contractors on the jobsite will be responsible to pay for the cost-plus fee to have a third-party contractor make the job site clean, neat, and orderly.
5. All Model Construction jobsites are TOBACCO FREE. All smoking, dipping, chewing, etc. must be done off site, in the area designated by Model Construction Superintendent. Please inform your crew(s), as this will be enforced.
6. Temporary restrooms are provided by Model Construction.
7. Disregard all reference to "General Contractor", "Trade Contractor", or "Subcontractor" in the Bid Documents, as the Scope of Work outlined herein takes precedence.
8. All work shall be performed by OSHA regulations and standards. All safety issues are to be corrected and paid for by this subcontractor.
9. All workers on Model Construction Job Sites should be OSHA ten hour trained or have the basic knowledge of OSHA laws and regulations.
10. All Job-Specific SDS Sheets for this Work Scope must be submitted to the Model Project Manager PRIOR to the start of work.
11. Weekly subcontractor meeting will be held in the job office. These meetings are MANDATORY! At least one member from the subcontractor (foreman, project manager, or someone with decision making authority) must be in attendance starting two weeks prior to the scheduled start date, and throughout the duration of your scope of work.
12. Working hours for this project are established as 7:00 AM to 3:30 PM Monday through Friday. If Subcontractors desire to work outside of these hours, prior approval must be granted by Model Construction Superintendent. If time is lost throughout the week, Subcontractors are expected to work Saturday to make up lost production. Otherwise, Subcontractors shall be expected/permitted to work Saturday, Sundays and/or Federal Holidays as required to maintain Schedule commitment.
13. All work shall be completed in strict compliance with the Bid Documents and Manufacturer's written instruction.

OUTLINE SCOPE OF WORK

14. Any work not covered in the base contract must be approved by Model Construction before subcontractor proceeds with the work. A daily ticket must be signed by Model superintendent for all extra work. All extra tickets must be included in a Change Order Request and submitted on a weekly basis. No compensation will be paid to subcontractor for extra work until it is signed by the subcontractor and Model Construction.
15. Proactive thinking and coordination with Model Construction and other subcontractors is expected and required throughout this project.
16. Any functioning system turned off or disconnected during the day must be put back in service by the end of the workday. Workday is to be considered day or evening shift depending on where the work is taking place.
17. Provide close out documents, spare parts, O & M manuals, warranty, etc. upon completion of the scope of work.
18. Subcontractors shall register all warranties on behalf of the Owner. Subcontractor shall request any information needed for warranty registration from Model Construction.
19. Maintain and submit accurate as-built drawings upon completion.
20. Provide OSHA 300A at the end of this job documenting the hours logged by workers on the jobsite and any incidents that occurred on the jobsite.
21. Subcontractor is to provide a 1-year warranty for all work performed, stating on the day the certificate of occupancy is issued. This 1-year warranty must be officially submitted to Model Construction at the end of the project on company letterhead. Subcontractor shall register all warranties on behalf of the Owner.
22. Contractor shall visit the site and become familiar with existing conditions as they relate to the proposed work prior to submitting bid, ordering materials, etc.
23. Drawings and dimensions are plus/minus. Contractor responsible for verifying existing conditions, dimensions, etc., prior to commencing work. Report substantial discrepancies to Model Construction immediately, before continuing with work. Do not scale drawings.
24. Each contractor is responsible for performing work according to local, state, and national codes, as well as other regulations which apply to such work.
25. Removal or cutting of structural members is not permitted. Consult with Model Construction regarding repair or removal of structural items.
26. Materials to be installed must conform to the manufacturer's recommendations.
27. Hard hats, work boots, protective eyewear and gloves are required for all personnel on-site.
28. Final Payment will be paid after the contractor complies with submitting its completed company punch list, submitting completed signed copies of Model Construction punch lists, and providing all warranty paperwork to Model Construction.
29. Smoking, eating, and drinking are prohibited in undesignated areas.
30. All work shall be coordinated and scheduled by the contractor and Model Superintendent to ensure completion in accordance with the project schedule.
31. Cleaning and sweeping of public roadways for dust, mud, debris generated by Subcontractor's work.
32. All traffic control, safety barricades, permits etc. required for partial, temporary road closures or use for the duration of this work as required to prevent hazards to the public and all project subcontractors or visitors.
33. Multiple mobilizations as required to execute the project in accordance with the Schedule.
34. Material staging is to be coordinated with Model's superintendent. Locations must be approved by Model.
35. Materials that are approved to be stored inside need to be kept on a mobile rack, cart, or pallet. Tools should be kept in mobile, lockable gang boxes or toolboxes. Model is not responsible for lost, damaged or stolen tools.
36. Each contractor is responsible for compiling their own punch list, submitting a record of it to Model and completing it prior to the architect's punch list.

OUTLINE SCOPE OF WORK

PROCORE NOTIFICATION:

Model Construction will be using Procore as the construction management software. This is a free service to an indefinite number of project users. Procore has many collaborative features that offer various benefits to the project, as well as having benefits to individual users. For that reason, there are several requirements that will be expected of all contractors on the project.

1. All subcontractors will be required to complete the Subcontractor Procore Certification.
2. All users will be required to have an individual email with notification of arrival of new email messages.
3. All contractors will be required to utilize the collaborative tools within Procore. These include and are not necessarily limited to RFIs, Submittals, Document Management, Change Management, Drawings, Specs, Photos, Observations etc.
4. A foreman/superintendent for each contractor will be required to have an iPad or tablet with a mobile plan for daily use of the Procore mobile app. The app will require maintenance of updates as frequently as once a week.
5. All contractors will be required to utilize the safety and quality related tools within Procore (i.e., daily inspections, daily JSAs, weekly toolbox talks, jobsite orientations, photos, observations, etc.)

SCHEDULE NOTIFICATIONS (Applicable to all Subcontracts):

Subcontractors, Major Suppliers, and Model Construction will collaboratively develop the Project Schedule via a pull planning session. The Project Manager and Superintendent/Foreman for Model Construction and each Subcontractor and Major Supplier will attend the pull planning session. Subcontractors and Major Suppliers should expect to dedicate a full day actively engaged in pull-planning for each project. Once the Project Team has developed the Project Schedule, the Project Schedule will be incorporated into each Subcontract and Purchase Order via a no-cost change order.

All work shall be coordinated and scheduled per the attached project schedule (Exhibit C) and managed through General Contractor.

TRADE SPECIFIC SCOPES OF WORK:

The following provides an outline of the Scope of Work Model Construction anticipates per bid package. Model Construction is open to standalone and combination bids, however, requests that pricing is broken out per the bid packages below.

BP 3A – CONCRETE:

Subcontractor shall provide a turnkey, all-inclusive building Concrete scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. All Layout from established control points.
2. Provide all site concrete including:
 - A. Concrete dumpster pad, footers, and walls for dumpster surround.
 - B. Concrete sidewalks and integral curbs.
 - C. Provide exterior concrete walls at ramps and planter walls. Include gravel backfill for ramps and steps.
 - D. Provide exterior concrete steps.

OUTLINE SCOPE OF WORK

- E. Provide truncated domes at handicap ramps.
 - F. Provide installation of bollards; bollard material provided by others. Include installing 7 bollards at transformer pad per E300.
 - G. Provide parging of existing concrete retaining walls at northeast corner of site.
3. Includes all building concrete including:
- A. Footings.
 - B. Foundation walls.
 - C. Elevator pit slab and walls.
 - D. Slab on grade.
4. Subgrade will be provided at +/- 0.1'. From subgrade, include all excavation and backfill necessary to execute this scope of work. Backfill all excavations to restore subgrade.
5. Backfill interior side of foundation walls and elevator pit walls with granular fill; compact properly to minimize settlement.
6. Export all foundation spoils from project site.
7. Provide gravel subbase associated with slab on grade and site concrete.
8. Provide 15 mil vapor barrier at slab on grade.
9. Provide form work for concrete work, as required.
10. Rub exposed exterior concrete walls.
11. Provide all rebar, mesh and fiber mesh associated with concrete scope.
12. Provide expansion joints for concrete pavements per industry standards.
13. Provide concrete placement, including pumping, if required.
14. Dewatering as required to install footings/foundations.
15. Provide the footer drain at elevator pit and exterior ramps. Connect footer drain to storm system.
16. Provide R15 foundation / slab insulation where indicated.
17. Set all steel embeds, anchors, base plates, etc. furnished by others.
18. Provide grouting of steel base plates.
19. Provide concrete curing, as required.
20. Provide temperature control of concrete.
21. Coordination concrete cylinder with special testing consultant.
22. All appurtenances and accessories for a complete installation.
23. Protect adjacent finished surfaces to ensure concrete does not splatter and damage finish.
24. Cleaning and sweeping of public roadways for dust, mud, debris generated by Subcontractor's work.
25. All traffic control, safety barricades, permits, etc. required to execute this scope of work.
26. Furnish, install, and remove concrete washout pit. Concrete washout / mixing area will be designated by Model Superintendent. At a minimum, the washout / mixing area shall be bermed, sheathed with plastic to ensure washout does not enter rainwater and maintained by the Concrete contractor. At the end of Concrete operations and/or at the direction of the Model superintendent, the Concrete Subcontractor shall remove washout from the site.
27. Multiple mobilizations as required to execute the project in accordance with the Schedule.
28. Alternate:
- A. Provide pricing for concrete barrier curbs.
29. Unit Pricing:
- A. Provide pricing per CY to undercut unsuitable soils below footers and replace with 1,500 psi lean crete. Include hauling spoils offsite.
30. Exclusions:
- A. Steel embed materials
 - B. Bollard material
 - C. Light pole bases

OUTLINE SCOPE OF WORK

- D. Gypcrete
- E. Special testing
- F. Winter conditions
- G. Barrier curbs
- H. Joint sealants
- I. Transformer pad

BP 3B – GYPCRETE:

Subcontractor shall provide a turnkey, all-inclusive Gypcrete scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide 2,500 psi 1" Gypcrete on the second and third floors.
2. Provide gypcrete sealer material for application by the flooring contractor.
3. Provide two mobilizations for gypcrete scope.
4. Exclusions:
 - A. Pour stops.
 - B. Sound mat.

BP4 – MASONRY:

Subcontractor shall provide a turnkey, all-inclusive Masonry scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Layout from established control points.
2. Provide CMU at elevator shaft and stair walls.
3. Provide brick veneer. See A201 for brick selection.
4. Provide cast stone sills and cap. Utilize precut corners and sills for cast stone.
5. Provide masonry at monument sign per AS102.
6. Wash all brick veneer and cast stone upon completion.
7. Provide rebar and grouting for masonry as indicated.
8. Provide spray foam insulation at CMU cores where indicated on the drawings.
9. Provide rigid insulation in masonry cavities (i.e CMU walls with brick veneer)
10. Provide masonry wire and anchors.
11. Provide flashing of masonry.
12. Provide layout and placement of embeds and anchors (material provided by others).
13. Tool joints as required.
14. All hoisting, unloading and scaffolding, etc. necessary to complete this Scope of Work.
15. Grout and mortar washout / mixing area will be designated by Model Superintendent. The washout / mixing area shall be maintained by the Masonry contractor. At the end of Masonry operations and at the direction of the Model Superintendent, the Masonry Contractor shall remove washout from the site.
16. All dust control as required for masonry operations is to be included.
17. Temporary water bib will be made available. Consumption is by Model Construction. All hoses, fittings etc. required to perform your work shall be by the Masonry Contractor.

OUTLINE SCOPE OF WORK

18. The masonry contractor is responsible for the daily clean-up of their own work.
19. All traffic control, safety barricades, permits, etc. required to execute this scope of work.
20. Multiple mobilizations as required to execute the project in accordance with the Schedule.
21. Exclusions:
 - A. Winter conditions

BP 5 – STRUCTURAL STEEL / MISCELLANEOUS METALS:

Subcontractor shall provide a turnkey, all-inclusive Structural Steel / Miscellaneous Metals scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Furnish only miscellaneous metals:
 - A. Steel Lintels
 - B. Bollards at Dumpster Enclosure
 - C. Provide 7 bollards at Transformer per E300
 - D. Base plates and anchor bolts
2. Furnish and install:
 - A. Structural steel
 - B. Exterior galvanized steel railings and guardrails
 - C. Steel railings at stairwells
 - D. Steel elevator hoist beam
 - E. Roof access ladder with security door
3. All exterior steel to be galvanized.
4. Prime steel as indicated. Clean field welds, grinding marks, etc. after installation and touch up primer such that exposed steel is ready for final painting.
5. Drill, epoxy, and anchor as indicated, or provide anchor bolts and layout to the concrete sub to set.
6. Exclusions:
 - A. Elevator pit ladder
 - B. Stainless steel railings (all exterior railings shall be galvanized steel)

BP 6A – ROUGH CARPENTRY / STRUCTURAL WOOD FRAMING:

Subcontractor shall provide a turnkey, all-inclusive Rough Carpentry scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Layout from established control points.
2. Provide framing / rough carpentry for new 3-story building.
3. Provide floor and roof wood trusses.
4. Provide delegated design for floor and roof trusses.
5. Provide 5/8" OSB roof sheathing.
6. Provide 3/4" T&G floor sheathing.
7. Provide bearing and non-bearing wood framed walls.
8. Provide Zipwall sheathing and tape at exterior walls.
9. Provide prefabricated carpet grade wood stairs, landings, stringers, treads and risers.

OUTLINE SCOPE OF WORK

10. Provide wood soffit framing at building eaves and entrances.
11. Provide installation of vinyl windows (material provided by BP 8C)
12. Provide window flashing material.
13. Provide all exterior and interior blocking. Include blocking for bathroom specialties such as grab bars, mirrors, shower rod, towel bars, sanitary disposals, and toilet paper dispensers. Include blocking for handrails, wall mounted door stops and TV locations. Include additional framing for tub/shower wall anchoring (or layout at edge of tub for anchoring).
14. Provide all structural components (brackets, clips, hangers, Simpson anchors, fasteners, epoxy, etc.). as defined on the contract documents.
15. Drill & epoxy and wedge anchors as indicated.
16. Provide all fasteners required to complete BP 6A.
17. Include framing/blocking for attic access hatch, fan coil units, exhaust fans, etc.
18. Provide pressure treated lumber where indicated.
19. Frame openings for HVAC (duct), Electrical (panels) and plumbing trades. Coordinate closely with other trades. Frame openings for Architectural items such as medicine cabinets and fire extinguisher cabinets.
20. Provide engineered shop drawings as required for all engineered lumber and methods.
21. The contractor is responsible for the daily clean-up of their own work.
22. All hoisting, unloading, man/material lifts, rigging, etc. necessary to complete this Scope of Work.
23. Furnish & install fire blocking per code.
24. Stencil fire walls installed with this Scope of Work as indicated.
25. Pad down wood/metal beams for storefront systems RO.
26. Make safe vertical and horizontal openings in building by installing blocking, rails, guardrail, hole covers, etc.
27. Multiple mobilizations as required to execute the project in accordance with the Schedule.
28. Alternate:
 - A. Provide price for Zip Wall exterior sheathing in lieu of OSB/Tyvek wrap.
29. Exclusions:
 - A. Metal railings
 - B. Framing for interior dropped ceilings

BP 6B – EXTERIOR SIDING AND TRIMS:

Subcontractor shall provide a turnkey, all-inclusive Exterior Siding scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide prefinished 4" and 8" fiber cement lap siding and trim per A200 and A201.
2. Provide "wood look" Nichiha siding per A200 and A201.
3. Provide ventilated vinyl soffits at eaves and front entrance.
4. Provide caulking at fiber cement/brick joints and at windows within fiber cement siding.
5. Provide any/all siding and trims on the exterior are included in this scope. Any required sub-framing required by the siding manufacturer not shown on the drawings is to be included in this scope.
6. Alternate:
 - a. Provide deduct to provide unfinished lap siding in lieu of prefinished.

OUTLINE SCOPE OF WORK

BP 7A – WATERPROOFING

Subcontractor shall provide a turnkey, all-inclusive Waterproofing scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide below grade waterproofing and protection board at elevator pit walls and detail 4/A504.

BP 7B – INSULATION

Subcontractor shall provide a turnkey, all-inclusive Insulation scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide R-21 exterior wall thermal insulation per the drawings.
2. Provide Air Sealing Package as required by IEC and for performance of air infiltration testing.
3. Provide spray insulation at window in accordance with the drawings.
4. Subcontractor is responsible for the daily clean-up of their own work.
5. Include multiple mobilizations, as required, to complete the installation in accordance with the project schedule.
6. Provide supplemental temporary lighting, if required, to execute this Scope of Work.
7. Alternate:
 - A. Provide pricing for sound batt insulation at interior walls and floor joists.
8. Exclusions:
 - A. Attic insulation.
 - B. Spray foam in CMU cores of elevator shaft.
 - C. Rigid insulation at foundation walls and roof.

BP 7C – ROOFING, GUTTERS & DOWNSPOUTS

Subcontractor shall provide a turnkey, all-inclusive Roofing scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide 60 mil EPDM roofing system with minimum R-30 polyiso insulation. Provide tapered insulation per drawings.
2. Provide prefinished metal lined roof scuppers and downspouts.
3. Provide prefinished metal coping and metal fascia at elevator.
4. Provide flashing of all MEP roof penetrations per the drawings.
5. Provide roof walk pads per the drawings.
6. Provide 36" x 36" roof hatch.
7. Provide wood blocking for parapet caps at CMU walls.
8. Install in accordance with all manufacturer's written instructions to ensure warranties required by the Specifications are obtained.
9. Coordinate roofing work with mechanical, electrical, and plumbing drawings. Include flashing for all roof curbs, vents, etc.

OUTLINE SCOPE OF WORK

10. Exclusions:

- A. Aluminum Canopies
- B. Wood Blocking
- C. Roof Curbs

BP 7D – ACM PANELS

Subcontractor shall provide a turnkey, all-inclusive ACM Panel scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

- 1. Provide ACM panels and trim. See A200 and A201 for basis of design.
- 2. Provide vented metal soffit panel at entrances per drawing.
- 3. Provide any clips and fasteners for ACM panel installation.

BP 7E – JOINT SEALANTS

Subcontractor shall provide a turnkey, all-inclusive Joint Sealants scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

- 1. Provide joint sealants at masonry joints and masonry/siding joints.
- 2. Provide joint sealants of hollow metal door frames in masonry.
- 3. Provide joint sealants on exterior side of vinyl windows.
- 4. Provide joint sealants of louvers.
- 5. Provide joint sealants of exterior concrete expansion joints.
- 6. Exclusions:
 - A. Caulking of countertops, trim, aluminum storefront, and plumbing fixtures.

BP 8A – COMMERCIAL DOORS, FRAMES, & HARDWARE:

Subcontractor shall provide a turnkey, all-inclusive commercial Doors, Frames, and Hardware scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

- 1. Provide 3-sided hollow metal door frames at wood stud walls.
- 2. Provide welded hollow metal frames within masonry walls.
- 3. Provide hollow metal doors.
- 4. Provide prefinished solid core wood doors.
- 5. Provide door hardware associated with all wood and hollow doors.
- 6. Provide hollow metal frames for borrowed lites.
- 7. Include all staging, delivery, and shakeout for BP 8A.
- 8. Include trim, fasteners, sealants and all miscellaneous appurtenances and accessories for a complete installation.
- 9. Provide lock cylinders and keying for all doors including aluminum doors.
- 10. Exclusions:

OUTLINE SCOPE OF WORK

- A. Aluminum Door Hardware
- B. Glazing

BP 8B – ALUMINUM ENTRANCES AND STOREFRONT:

Subcontractor shall provide a turnkey all-inclusive Aluminum Entrances and Storefront scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide aluminum doors and glazing.
2. Provide aluminum storefront and glazing. Aluminum to be dark bronze.
3. Provide glazing in hollow metal frames, hollow metal doors, and wood doors as indicated.
4. Provide door hardware for aluminum doors.
5. See glass legend on A600.
6. Provide CR Laurence Cashier units and Pass Thru windows at Reception per A301.
7. Provide CR Laurence bullet proof exchange windows per detail 28/A301.
8. Exclusions:
 - A. Vinyl windows

BP 8C – VINYL WINDOWS:

Subcontractor shall provide a turnkey all-inclusive Vinyl Window scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide single hung vinyl windows. Basis of Design is Quaker V250 series. See sheet A601.
2. Provide windows with limiters and ADA hardware as indicated.
3. Include tempered glass in windows where required by code.
4. Exclusions:
 - A. Installation - By BP 6A
 - B. Window flashings

BP 9A – METAL FRAMING, DRYWALL & CEILINGS:

Subcontractor shall provide a turnkey, all-inclusive Metal Framing, Drywall, Acoustic Ceiling scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Metal framing:
 - A. Provide 7/8" furring channels at the underside of floor trusses.
 - B. Provide resilient channel as indicated at interior walls.
 - C. Provide metal framing for soffits and bulkheads.
2. Provide drywall on walls in accordance with the drawings.
3. Provide drywall ceiling systems in accordance with the drawings.
4. Finish drywall walls and ceilings to a level 4 finish.
5. BP 9A is responsible for sealing the tops, bottoms, and sides of all drywall assemblies.

OUTLINE SCOPE OF WORK

6. Provide "Pre-Rock" installation as required.
7. Provide sound batt insulation at floor joists per the drawings.
8. Provide sound batt insulation within interior walls per the drawings.
9. Provide FRP at mop sinks.
10. Provide acoustical ceilings with tegular tiles.
11. Include all fasteners, sealants, trim and miscellaneous appurtenances, and accessories for a complete installation.
12. After the prime coat of paint is installed, the drywaller is to perform a quality control walkthrough and touch up defects in the drywall finishing or any drywall dents prior to the first coat of paint. Use dye in the drywall mud so the painter can identify the touchup locations and re-prime. Also include a round of touchup immediately prior to final paint.
13. Alternate:
 - A. Provide price to install all hollow metal frames, doors, and hardware. Assume all hardware will be loose and not preinstalled.
 - B. Provide price for sound insulation at interior walls and floor joists.

BP 9B – FLOORING & TILE

Subcontractor shall provide a turnkey, all-inclusive Flooring and Tile scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. All flooring in accordance with the Finish Legend and Specifications.
2. Provide LVT plank flooring with 20 mil wear layer.
3. Provide 12" x 24" ceramic floor tile. Include a material allowance of \$2.50/SF.
4. Provide 4" bullnosed ceramic base.
5. Provide 4" resilient base.
6. Provide rubber stair treads and risers.
7. Provide carpet tile. Include a material allowance of \$25.00/SY.
8. Provide walk off carpet tile.
9. Apply gypcrete floor sealer prior to floor installation. Gypcrete sealer to be provided by BP 3B and installed by flooring contractor.
10. All underlayment and/or minor prep in accordance with manufacturer's instruction.
11. Waterproof and crack isolation membrane.
12. Seal tile and grout as required.
13. All sealants required for a complete installation.
14. Transition strips, reducer strips, and moldings.
15. Expansion joints where required by manufacturer's instruction.
16. Flooring to be installed/refinished completely under cabinets and restroom vanities in all areas.
17. Installation in accordance with manufacturer's written instruction.
18. Provide supplemental lighting necessary to execute this scope of work.
19. Include all fasteners, sealants, trim and miscellaneous appurtenances, and accessories for a completion installation.
20. Cover new flooring with ram board after installation.
21. Exclusions:
 - A. Sealed concrete

OUTLINE SCOPE OF WORK

BP 9C – EPOXY FLOORING

Subcontractor shall provide a turnkey, all-inclusive Flooring and Tile scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide epoxy flooring at Central Bathing 342.
2. Exclusions:
 - a. Epoxy base

BP 9D - PAINTING

Subcontractor shall provide a turnkey, all-inclusive Painting scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Interior painting includes walls, ceilings, hollow metal doors, hollow metal frames, steel handrails, stair stringers, and wood wall caps.
2. Exterior painting includes steel lintels, hollow metal doors/frames, bollards, dumpster gate, and existing concrete retaining walls.
3. Include concrete floor sealer, where indicated.
4. Provide caulking at joints of dissimilar painted materials and at interior side of vinyl windows.
5. Clean, prep, and prime all surfaces prior to painting.
6. Work also includes one "touch-up" / Owners Punchlist in all areas prior to move-in (after final paint).
7. Supplemental lighting necessary to execute this scope of work.
8. Provide attic stock for each paint color and sheen.
9. Include a full prime coat, a spot prime after drywall/CMU/plaster touch up, and two full finish coats. Final finish system shall only be applied when coordinated with Model Construction. Touch up will also be required for punch list execution.
10. Mask surfaces that are not scheduled for paint / finish. Securely cover sprinkler heads, lights, grilles/diffusers, etc. while painting. Remove any and all overspray.
11. Alternate:
 - A. Provide price to paint fiber cement lap siding and trim.
12. Exclusions:
 - A. Finishing of cabinets
 - B. Painting wood doors

BP 10A - SPECIALTIES:

Subcontractor shall provide a turnkey, all-inclusive Specialties scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Toilet and bath accessories.
 - A. Paper towel dispensers.
 - B. Toilet paper holders
 - C. Grab bars.

OUTLINE SCOPE OF WORK

- D. Towel bars.
 - E. Shower curtain and rods.
 - F. Sanitary napkin disposals
 - G. Frameless mirrors
 - H. Mop and broom holder
2. Corner guards
 3. Fire extinguishers and cabinets.
 4. Recessed knox box 3200 series, color bronze.
 5. Include all fasteners, anchors, tapes, sealants, miscellaneous appurtenances, and accessories for a complete installation in accordance with Specifications and Manufacturer's written instruction.
 6. Exclusions:
 - A. Shower seats and grab bars at ADA showers.

BP 10B – ALUMINUM CANOPY:

Subcontractor shall provide a turnkey, all-inclusive Aluminum Canopy scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide aluminum canopies with hanger rods at door entries. See Roof Plan A103 for locations.
2. Provide stamped engineered drawings for canopies.
3. Include all fasteners, anchors, tapes, miscellaneous appurtenances, and accessories for a complete installation in accordance with Bid Documents and Manufacturer's written instruction.

BP 10C – SIGNAGE:

Subcontractor shall provide a turnkey, all-inclusive Signage supply scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide dimensional letter at the monument sign per AS102.
2. Provide internally illuminated building signage per A200.
3. Provide interior room signage per A900-A902.
4. Include all fasteners, trim, and miscellaneous appurtenances and accessories for a complete installation in accordance with Bid Documents and Manufacturer's written instruction.

BP 10D – OPERABLE PARTITION

Subcontractor shall provide a turnkey, all-inclusive Operable Partitions supply scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents

The inclusions of this Scope of Work are generally outlined below:

1. Provide operable partition with standard fabric at Room 109/111.
2. Exclusions:
 - a. Doors
 - b. Overhead Support

BP 11 – APPLIANCES - NOT CURRENTLY BIDDING**BP 12A - WINDOW TREATMENTS:**

Subcontractor shall provide a turnkey, all-inclusive window treatments scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide 2" faux wood blinds on all windows in accordance with the specifications.
2. Provide field measuring for window treatments.
3. All fasteners, anchors, hardware and miscellaneous appurtenances and accessories for a complete installation.
4. Clean up dust, debris, packaging daily.
5. Alternate:
 - A. Provide price for roller shades in lieu of 2" faux blinds.
6. Exclusions:
 - A. Window treatments at aluminum storefront.

BP 12B – CASEWORK & COUNTERTOPS:

Subcontractor shall provide a turnkey, all-inclusive Casework and Countertop scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide plastic laminate casework.
2. Provide plastic laminate countertops with backsplashes.
3. Provide solid surface windowsills.
4. Provide solid surface countertops and caps per drawings.
5. Include Group 1 colors for plastic laminate and solid surface.
6. Provide cultured marble countertop with integral sinks at bathrooms per drawings.
7. Provide wood veneer wall panels at Reception.
8. Provide wood wall caps at stairwells.
9. Include fillers and finished end panels where indicated.
10. All fasteners, anchors, hardware and miscellaneous appurtenances and accessories for complete installation.

BP 14A – ELEVATOR

Subcontractor shall provide a turnkey, all-inclusive Elevator scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide elevator permit and inspections.
2. Provide a hydraulic elevator with 3,500# capacity. Basis of Design to be TK Elevator Endura HMRL.
3. Include unloading, shakeout, and delivery into the building.
4. Provide all associated elevator equipment, accessories, cab finishes, rails, rail brackets and supports.

OUTLINE SCOPE OF WORK

5. Provide hoisting required to complete this Work.
6. Provide all unloading and material handling.
7. Provide two (2) days of elevator mechanic time to work with mason,
8. Provide elevator pit ladder.
9. Provide owner training.
10. Provide one (1) year of maintenance.
11. Testing as required to prove functionality of installed systems.
12. Upon completion, install pads within cab to protect finishes.
13. Exclusions:
 - A. Flooring in elevator cab

BP 21 – FIRE SUPPRESSION:

Subcontractor shall provide a turnkey, all-inclusive fire suppression scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide design in accordance with NFPA 13.
2. Provide drawings and permits required to execute the Scope of Work.
3. Core drill or hole saw all penetrations associated with this scope of work.
4. Connect to flange immediately inside of building.
5. Provide butterfly valve with tamper switch, riser check valve and flow switch.
6. Provide fire pump, jockey pump, standpipes, and controllers, as required.
7. Provide any control wiring associated with equipment (if required).
8. Provide brass upright heads at exposed areas, concealed sprinkler heads at finished ceilings and sidewall sprinkler heads per drawings.
9. Provide all escutcheons, sleeves, fasteners, anchors, sealants, fire caulking, hangers, supports, and miscellaneous appurtenances and accessories for a complete installation.
10. Provide labeling of sprinkler components.
11. Provide owner training.
12. Provide testing as required to prove functionality of installed systems.
13. Provide supplemental lighting necessary to execute this scope of work.
14. Exclusions:
 - A. Exterior Water Line

BP 22A – PLUMBING:

Subcontractor shall provide a turnkey, all-inclusive plumbing scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Layout from established control/building lines.
2. Provide plumbing permit and inspections.
3. Provide all plumbing fixtures including all sinks.
4. Provide fiberglass bath surrounds.
5. Provide ADA shower bases and surrounds.
6. Provide interior domestic water, waste, vent & gas piping.

OUTLINE SCOPE OF WORK

7. Provide exterior gas piping.
8. Provide elevator pit sump pump.
9. Provide roof drains.
10. Provide concrete pads for plumbing equipment per drawings.
11. Provide all excavation, bedding, backfill, compaction, etc. required to execute this scope of work.
12. Provide hauling plumbing spoils offsite.
13. Connect to exterior sanitary line 5' outside of building.
14. Connect to water flange inside of building.
15. Coordinate with BP 3 for floor drain and trench drain elevation and installation.
16. Coordinate with BP12B for countertop cutouts and penetrations for sinks and faucets.
17. Provide all insulation associated with the plumbing scope.
18. Core drill or hole saw all penetrations. Sleeve/collar/seal/firecaulk as required.
19. All fasteners, anchors, sealants, fire sealants/collars, hangers, supports, insulation and miscellaneous appurtenances and accessories for a complete installation.
20. Demonstrative training of maintenance staff on operation of systems and fixtures.
21. Supplemental lighting necessary to execute this scope of work.
22. Equal alternate fixtures are strongly encouraged.
23. Exclusions:
 - A. Radon/Vapor mitigation
 - B. Tap fees
 - C. Exterior Water Line

BP 22B – VAPOR MITIGATION

Subcontractor shall provide a turnkey, all-inclusive plumbing scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide design build vapor mitigation system.
2. Provide stamped engineering drawings.
3. Provide under slab piping and vent piping
4. Provide fans as required.
5. Inspect vapor barrier installation.

BP 23 – HVAC:

Subcontractor shall provide a turnkey, all-inclusive HVAC scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Coordinate HVAC inspections.
2. Provide HVAC equipment including rooftops units, VAV boxes, ductless splits, electric heaters, fans, etc.
3. Layout from established control/building lines.
4. Provide roof curbs/rails for HVAC equipment.
5. Provide refrigerant and condensate piping.
6. Provide all air devices and dampers including diffusers, grilles, fire dampers, smoke dampers, radiant dampers, etc.

OUTLINE SCOPE OF WORK

7. Provide mechanical control devices such as thermostats, CO sensors, etc. as indicated. Include all control wiring/cabling.
8. Provide insulation associated with HVAC scope of work.
9. Provide wall and roof vent/exhaust caps. Include Zipwall tape at exterior wall penetrations.
10. Core drill or hole saw all HVAC penetrations. Sleeve/collar/seal/firecaulk as required.
11. Provide all sealants, fire sealants, hangers, fasteners, and miscellaneous appurtenances and accessories for a complete installation.
12. Provide caulking of all duct boots to the drywall with latex caulk or fire caulk (depending on fire assembly rating) to prevent air leakage.
13. Provide duct sealing.
14. Provide roof curbs, equipment pads, stands and hangers as indicated.
15. Provide new filters prior to substantial completion and clean all equipment inside and out including coils.
16. Include duct access panels where indicated.
17. Provide all louvers, wall caps and brick vents for HVAC work.
18. Provide certified air balancing.
19. Provide demonstrative training of maintenance staff on operation of systems and equipment.
20. Provide supplemental lighting as necessary to execute this scope of work.
21. Exclusions:
 - A. HVAC Permit
 - B. Undercutting Doors
 - C. Roofing

BP 26 – ELECTRICAL

Subcontractor shall provide a turnkey, all-inclusive electrical & special systems scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide electrical permit and inspections.
2. Install and maintain temporary lighting and power throughout the course of the project. Temporary lighting shall be installed and maintained to meet or exceed OSHA minimum lighting levels. Temporary power to be brought
3. Provide new electrical service in accordance with the drawings.
4. Provide site electric including excavation, conduit, pull boxes, bedding, warning tape, concrete encasement (if required), backfill, light poles/fixtures, light pole bases, etc.
5. Provide concrete transformer pad and generator pad.
6. Haul spoils offsite generated from underground electrical work.
7. Provide electric metering per plans.
8. Provide power in accordance with the drawings. Coordinate with other trades for their power requirements.
9. Provide lighting and lighting controls in accordance with the drawings.
10. Provide fire alarm system complete, including delegated design and permit.
11. Provide elevator shunt trip breaker.
12. Provide natural gas generator with transfer switch.
13. Include conduit where wiring / cabling cannot be concealed in gypsum board partitions or ceilings.
14. Include pathways for thermostat control wiring, voice/data, access control, and security cameras.
15. Core drill or hole saw all penetrations. Sleeve/collar/seal/firecaulk as required.
16. Provide all miscellaneous appurtenances and accessories for complete installation.
17. Provide demonstrative training of maintenance staff on operation of systems and equipment.
18. Blocking for light fixtures or any electrical equipment is to be installed by the electrician.

OUTLINE SCOPE OF WORK

19. Caulk all electrical boxes (lights, switches, outlets, panels) to the drywall with latex caulk or fire caulk (depending on fire assembly rating) to prevent air leakage.
20. Cap smoke detectors and then remove them at inspections.
21. All traffic control, safety barricades, permits, etc. required to execute this scope of work.
22. Exclusions:
 - Duke Energy fees
 - Bollards at transformer
 - Access control
 - Security cameras
 - Audio visual
 - Structural cabling
 - J Hook pathways

BP 28 – SPECIAL SYSTEMS – NOT CURRENTLY BIDDING

BP 31A – DEMOLITION, EXCAVATION & UTILITIES – NOT CURRENTLY BIDDING

BP 31B – SEGMENTAL RETAINING WALL

Subcontractor shall provide a turnkey, all-inclusive Earthwork & Utilities scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide new Allan Block or equal segmental retaining wall.
2. Provide excavation and backfill for retaining wall.
3. Provide footer drain at base of retaining wall and drain to daylight.
4. Provide engineered drawings for segmental retaining wall if required by building department.
5. Exclusions:
 - A. Layout

BP 32A – ASPHALT PAVING

Subcontractor shall provide a turnkey all-inclusive Asphalt Paving scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Layout from established control points.
2. Provide gravel subbase at asphalt locations.
3. Provide asphalt paving including base course and surface course. Base course to be installed in 2025; surface course to be installed in Spring 2026.
4. Provide cleaning of base course prior to installation of tack coat / surface course.
5. Provide tack coat.
6. Provide striping of asphalt.
7. Provide parking blocks.
8. Provide handicap parking signs.

OUTLINE SCOPE OF WORK

9. Alternates:
 - A. Provide pricing for concrete barrier curbs at parking lot.

BP 32B – FENCE & GATES

Subcontractor shall provide a turnkey all-inclusive Fencing scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide dumpster gate including steel frame, gate posts, and fiber cement cladding.
2. Provide wood grain vinyl fencing and gate per keynote 32A and 32B on sheet A100.
3. Excavate for fence posts and cleanup spoils.
4. Exclusions:
 - A. Bollards
 - B. Layout

BP 33 – LANDSCAPING

Subcontractor shall provide a turnkey all-inclusive Landscaping scope of work for this project including but not limited to all labor, material, management, overhead, submittals, coordination, tools, equipment, applicable taxes, etc. This scope of work shall be in strict conformance with the Bid Documents.

The inclusions of this Scope of Work are generally outlined below:

1. Provide plantings and planting soil per landscaping drawings.
2. Provide seed and straw.
3. Provide 30 days of watering. Include hoses, sprinklers and timers.
4. Exclusions:
 - a. Topsoil